



SEMI-CONDUCTOR LABORATORY
(Department of Space, Govt. of India)
Sector 72, SAS Nagar 160071 Pb. (India) Ph: 91-172-2237401-10

SUB: REQUEST FOR QUOTATION (RFQ) FOR PROVIDING AND FIXING OF PVC TILE FLOORING AT SCL, S.A.S. NAGAR.

Sealed quotations as per enclosed Bill of Quantities (BOQ) are invited for the above-mentioned work. The commercial terms and conditions are as follows:

- 1) Time of completion of the work will be 7 (seven) days to be reckoned from the date of award of work by SCL.
- 2) Rates to be inclusive of all taxes, VAT, duties, octroi, etc.
- 3) Contractor to submit catalogue of the PVC tile flooring offered.
- 4) Quotation to remain valid for a period of 30 days from the date of opening.
- 5) Rates to remain firm during the duration of the work as well for the extended period, if any.
- 6) The rates should be quoted in the enclosed schedule of quantities and duly signed by the contractor.
- 7) The contractor shall guarantee the work for any material or workmanship defect for a period of six months.
- 8) Contractor may visit the site before quoting the rates so as to acquaint with actual site conditions.
- 9) Payment shall be released within ten days after the satisfactory completion of work and certification by engineer-in-charge.
- 10) The Contractor shall have ESI/PF code/Account number and deposit the ESI/PF in their ESI/PF account number only.**

Sealed quotations super-scribing "**QUOTATION FOR PROVIDING AND FIXING PVC TILE FLOORING**" must reach the office of the undersigned on or before 22.05.2008 by 1500 hrs (3.00 PM). The quotations will be opened on the same day at 1530 hrs (3.30 PM) in presence of quotationer(s) who wish to be present.

HEAD (CMD)
SEMI-CONDUCTOR LABORATORY
SECTOR – 72, SAS NAGAR
PHONE: (0172)- 2237401-09

SCHEDULE OF QUANTITIES

SR. NO.	ITEM DESCRIPTION	QTY.	RATE (RS.)	AMOUNT (RS.)
01.	<p>PVC Tile Flooring:</p> <p>Providing and fixing of 1.5mm thick PVC tile flooring of size 1' x 1' of approved make/shade such as Tusker/Poly Floor/Royal House on the existing floor including preparation of surface with POP so as to make the surface free from any undulations, fixing the PVC tiles with Dunlop S-758 or Fevicol SR-998, rolling with light wooden roller weighting 5 kg., all complete as per the direction of engineer-in-charge. Rates to be inclusive of all wastages, taxes, VAT, carriage, octroi, labour etc.</p>	35 SQM		
02.	<p>Providing and fixing of 1.5 mm thick PVC tile skirting (height - 5") of approved make/shade such as Tusker/Poly Floor/Royal House on the existing wooden partition, fixing with Dunlop S-758 or Fevicol SR-998, all complete as per direction of engineer-in-charge. Rates to be inclusive of all wastages, taxes, VAT, carriage, octroi, labour etc.</p>	20 RM		